



Completed full-width road reinstatement



Installation of new
sanitary sewer

Sykes Street is the main thoroughfare (Highway 26) through the Municipality of Meaford.

Sykes Street Sanitary Sewer and Watermain Replacement Municipality of Meaford

In 2002, the Municipality of Meaford retained the Ainley Group to replace the trunk sanitary sewer and trunk watermain on Sykes Street between Bayfield Street and Cook Street together with the full-width road reinstatement, a distance of approximately 400 metres. Since Sykes Street is the main thoroughfare (Highway 26) through the Municipality of Meaford requiring uninterrupted access to the adjacent businesses, regular contact with business owners and tenants was a priority before and during construction. Traffic flow was maintained in both directions at all times, with reductions to one lane using the appropriate on-site flagging personnel. Two-way traffic was reinstated at the end of each working day.

The scope of work for the project included final design and approvals, agency review and consultations, Council presentations, utility coordination and site supervision. In addition, at the request of the client, supplementary works included the resurfacing of Berry Street, a municipal office parking-lot layout and miscellaneous paving. The construction period was from May to July of 2002 with substantial completion on July 24, 2002.

Project Facts

Client: Municipality of Meaford

Scope of Work:

- Final design
- Agency review and consultations
- Council presentations
- Utility coordination
- Site supervision:
 - Removal and replacement of asphalt paving
 - Replacement of sanitary sewer with provision for temporary by-pass pumping
 - CCTV inspection of sewer
 - Connection of new watermain to existing main by 'Live Tap' method complete with valve.
 - Traffic control – maintain access to commercial properties at all times
 - Plugging of all abandoned pipes with concrete.

Project Cost: \$560,000 (2002)